
## **SECTION 121.00**

## FIRE HYDRANT INSTALLATION



## NOTES:

- 1. All construction shall be in accordance with the District's Construction Standards.
- 2. For allowable fire hydrants, valves, pipes, and fittings, see materials list Section 100.00.
- 3. For hot tap requirements see Section 100.70.
- 4. Hydrant bury depth may vary with prior approval of the District's Engineer.
- 5. Hydrant shall be covered with an approved bag until accepted and placed in service.
- 6. A minimum distance of 3 ft shall be clear of all vegetation and other obstructions around the fire hydrant, per Uniform Fire Code Section 10.206.
- 7. No underground utility shall be located within 48" each side of fire service trench.
- 8. No primary electric vault, above -ground electric service cabinet, or street light shall be installed within seven (7) ft of the fire hydrant. Where restrained-joint fittings are used, which eliminates the need for a thrust block, this distance may be reduced to three (3) feet.

Section 121.00 – Fire Hydrant Installation August 19, 2020

Centerville CSD

Approved

District Manager

Centerville CSD		District M	District Manager			
Section 121.00 – Fire Hydrant Installation August 19, 2020		Approved:				
			NOV O PROTESTAL I POULIU AND A TIME MANAGEMENT OF THE PARTY OF THE PAR			